

SCHEDULE OF UNIT PRICES
ALL-CR 77-5.50 (1-28-19)

PID No. 104252

42	511	CLASS QC1 CONCRETE, ABUTMENT INCLUDING FOOTING, AS PER PLAN	47	CY		
43	512	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	96	SY		
44	SPECIAL	SPECIAL - WATERPROOFING, MISC.: POLYCARB MARK 156 BOX BEAM WATERPROOFING SYSTEM (OR APPROVED EQUAL)	115	SY		
45	515	PRESTRESSED CONCRETE NON-COMPOSITE BOX BEAM BRIDGE MEMBERS, LEVEL 1, B17-48, AS PER PLAN	8	EACH		
46	516	1" PREFORMED EXPANSION JOINT FILLER	114	SF		
47	516	2" DEEP JOINT SEALER, AS PER PLAN	80	FT		
48	SPECIAL	SAWING & SEALING BIT. CONCRETE JOINTS, AS PER PLAN	74	FT		
49	516	1/8" PREFORMED BEARING PAD, AS PER PLAN	16	EACH		
50	516	ELASTOMERIC WITH INTERNAL LAMINATES ONLY (NEOPRENE), AS PER PLAN 2"x7"x11"	32	EACH		
51	517	RAILING (TWIN STEEL TUBE)	69	FT		
52	518	POROUS BACKFILL WITH FILTER FABRIC	1	LS		
53	613	LOW STRENGTH MORTAR BACKFILL	58	CY		
54	SPECIAL	STEEL DRIP STRIP	69	FT		
55	518	6" PERFORATED CORRUGATED PLASTIC PIPE	94	FT		
56	518	6" NON-PERFORATED CORRUGATED PLASTIC PIPE	44	FT		
57	523	DYNAMIC LOAD TESTING	1	EACH		

MAINTENANCE OF TRAFFIC

58	616	WATER	1	MGAL		
----	-----	-------	---	------	--	--

INCIDENTALS

59	614	MAINTAINING TRAFFIC	1	LS		
60	623	CONSTRUCTION LAYOUT STAKES AND SURVEYING	1	LS		
61	624	MOBILIZATION	1	LS		

GRAND TOTAL